

HB2014

East Lansing, MI

10-14 November 2014

54th ICFA Advanced Beam Dynamics

Workshop on High-Intensity,
High Brightness and
High Power Hadron Beams


Initial commissioning of ion beams at SPIRAL2

Patrick Bertrand

On behalf of the SPIRAL2 accelerator team

Summary


- SPIRAL2/GANIL layout and baseline
- SPIRAL2-NFS-S3 building/infrastructures
- Installation of the SPIRAL2 accelerator
- Beam commissioning strategy
- Conclusion



GANIL/SPIRAL2 Layout and mid term roadmap

Phase1 (2015-)


Increase the intensity of stable beams
High intense neutron source
($\text{HI} \leq 10^{15}$ pps, p-Ni)



A National & EU priority

SPIRAL1 Upgrade (2016-)
New light RIBs from beam/target fragmentation

	Q/ A	I (mA)	Energy (Mev/u)	Max beam Power (KW)
Protons	1/1	5	2 - 33	165
Deuterons	1/2	5	2 - 20	200
Ions	1/3	1	2 - 14.5	45
<i>Ions (option)</i>	<i>1/6</i>	<i>1</i>	<i>2 - 8</i>	<i>48</i>



Nov. 2010



Feb. 2011



May 2011



Oct. 2011

May 2012



Oct. 2012



Key figures of SPIRAL2 Building construction...

CIVIL ENGINEERING / 06/2011 TO 07/2013



KEY FIGURES

14 000 m³ concrete

2200 T steel reinforcement

280 000 hours

SPIRAL2 Building...



Building and infrastructures Work Packages...






Water cooling system

Nuclear ventilation




Simplified planning of SPIRAL2


Building construction...



Installation of SPIRAL2 accelerator




D/p ECR source



HI LEBT1



Power supply...




LEBT1 / LEBT2 connection

RFQ: The 5 segments assembled !!!



Bead pull tests began last week ..

SC LINAC: 88 MHz QWR cavities with short cryomodules, and warm focusing sections...



12 low beta cryomodules (0.07) and 7 high beta cryomodules (0.12)
 $L \approx 35 \text{ m}$



Assembly test
Cryo A + Warm section

Cryomodule	A	B
Valve-to-valve length [mm]	610	1360
# cavities	12	14
f [MHz]	88.05	88.05
β_{opt}	0.07	0.12
Epk/Ea	5.36	4.76
Bpk/Ea [mT/MV/m]	8.70	9.35
r/Q [Ω]	599	515
Vacc @ 6.5 MV/m & β_{opt}	1.55	2.66
Lacc [m]	0.24	0.41
Beam tube \varnothing [mm]	38	44

LINAC cavities, cryomodules and couplers




A

IRFU/Saclay



GANIL/Caen
(amplifiers)

B




IPNO/Orsay



LPSC/Grenoble
(couplers)






■ Cavities:

- All cavities qualified on vertical cryostat

■ Cryostats:

- 8 cryomodules assembled and tested
- 2 cryomodules delivered at GANIL
- Cryomodule number 9 ready to be tested very soon
- All **CMA** to be delivered to GANIL before **March 2015**



■ Cavities:

- All cavities have been qualified without and with plunger

■ Cryostats:

- 5 cryomodules qualified
- These 5 cryomodules delivered at GANIL
- **Last 2 cryomodules B to be transported to GANIL before December 2014**



All couplers have been processed
and conditionned

And LINAC Warm Sections..



Quadrupole assembly


Magnetic measurements



All vacuum boxes
ready

Box + qpole
assembly...

Insertion of one BPM
(BPMs = IPNO & BARC)



09/2014



RF transmission lines and circulators (linac corridor)



Solid State amplifiers

RED 09/2014

First cryomodule to be installed **17 November**



- All dipoles at GANIL and measured...
- All quadrupoles at GANIL, and all phase1 quads measured
- All Steerers at GANIL
- All Power Supplied at GANIL
- RMN & Hall probe system : under test (on-line monitoring)




RMN & Hall probe system

HEBT transfer lines



HEBT installation



- 21 Hall probes every cm in a thermostated box (35°)
- Measurement mesh : 5mm

200 KW Main Beam Dump (IPN Lyon)



3D Virtual view



Copper pieces



Beam Dump segments




Beam Dump segments






Cooling tubes


Earthquake Simulations (cryoA)



Sismic spectrum





Exemple of one mode



Elcom profile



Earthquake Simulations (RFQ)



Beam Commissioning Strategy

- Step 1: **beam pre-conditionning of ECR sources and LEBTs**
at LPSC/Grenoble and IRFU/Saclay
 - . **Collaboration** between teams
 - . **Validation** of the Design et the beam dynamics
 - . Run a maximum of **technical and assembly tests** in laboratories and/or with companies
 - . **Gain time** for the installation/tests at GANIL/SPIRAL2 site
- Step 2: **complete injector beam commissioning** at SPIRAL2/GANIL
- Step 3: Complete MEBT, + **Linac beam commissioning** using the HEBT1 towards the Beam Dump
- Step 3: **Day-1 experiment**, with NFS

STEP 1: Phoenix-V2+LEBT1 beam tests (at LPSC Grenoble)




20 μ Ae Ni 19+ obtained

RESULTS FOR GASES		
	I max for Q optimum	I max for Q/A 1/3
4He	> 2.4 mA 2+ non opt.	> 2.4 mA 2+ non opt.
16O	1.3 mA 6+	1.3 mA 6+
40Ar	450 μ A 9+ 350 μ A 11+	175 μ A 12+ Isotope 36


		70 μ A 13+ Isotope 40

		22 μ A 14+ Isotope 40
86Kr	110 μ A 17+	non measurable

STEP 1: Phoenix-V2+LEBT1: technical and beam tests (Grenoble)



Simulation



Beam test

stable 62 kV reached

$^{16}\text{O}^{6+}$ at 53.33.kV

Source Voltage : 53.33 kV


Q/m : 1/2.66

Beam Intensity : 1.3 mA


Measured emittances
($\pi.\text{mm.mrad norm.rms}$)

Horizontal : 0.25
Vertical : 0.14



STEP 1 : Phoenix-V2 + LEBT1: Optimisation of emittances (Grenoble)




Sextupole OFF



Sextupole ON





2nd order dipole aberration
correction with sextupole




STEP 1: Phoenix-V2 + LEBT1: Purification of the beam (Grenoble)

Milestone « Separation 100 » → OK


Experimental validation of the line separation power (> 100 in q/A), using a Xenon beam and separating $^{132}\text{Xe}^{25+}$ (~10uA) from « pollutant » $^{16}\text{O}^{3+}$ (~300uA)



Separation slits opened




Separation slits closed (+/-5mm)



STEP 1: Phoenix-V2 Nickel Beam production with LCO

- O₂ buffer gas , 0.9 kW RF injected (1.7 kW emitter)
- Max. oven temperature reached (~1500 °C) => limited evaporation => limited Ni intensity
- 1 pμA Q/A=1/3 produced => suitable for first physics experiments at SPIRAL2
- Result can be enhanced with a larger evaporation rate
- A new higher temperature/higher capacity oven is under study at GANIL ($\varnothing 20$)



1 pμA $^{58}\text{Ni}^{19+}$
Q/A=1/3 beam

Ion	Charge state	Intensity (μA)
^{58}Ni	$^{19+}$	20
^{58}Ni	$^{20+}$	11
^{58}Ni	$^{21+}$	4




STEP 1: Phoenix-V2 Calcium Beam production with LCO

N₂ buffer gas

- Dominant parasitic plasma/microwave heating of the oven
- RF limited to ~450 W injected (800 W emitter)
- Above this RF value: over-evaporation and charge state distribution degradation
 - ~10 W of parasitic heating (plasma/microwave)
 - 0.4 W of normal oven resistive heating only ($\Delta T \sim 50^\circ C$!)
- 1 p μ A Ca¹⁶⁺ demonstrated => suitable for first SPIRAL2 experiments
- Performance can be improved by using a dedicated low temperature oven (see next slide)



Very Limited source tuning!




1 p μ A $^{48}Ca^{16+}$
Q/A=1/3 beam

Ion	Charge state	Intensity (μ A)
^{40}Ca	13^+	48
	14^+	40
	15^+	30
	16^+	16

STEP 1: new Phoenix-V3 under development... (Grenoble)




- Conceptual design ✓
- Detailed drawing ✓
- Quote ✓
- Purchase orders ✓
- Parts delivery under progress...
- Source Assembly expected in November 2014
- First beam: January 2015
- Gas commissioning, metal beams : 01→10/2015



GOAL:

- ✓ Increase the Plasma Chamber ($0.7 \rightarrow 1.4$ liter)
- ✓ Ø 20 mm oven capability


STEP 1: negative peaks observed!



Solution: Additional piece of Tantalum at slit extremity

Beams with different q/As





STEP 1: Deuteron/proton Beam tests with 2.45 GHz ECR source + LBE2 + LBEC (at IRFU/Saclay)



- LBEC beam line was added in 2011 with all instrumentation and Interlocks. **(up to RFQ entrance)**
- **More than 5 mA proton or Deuteron**
- beam conducted to **end LBEC** in September 2011
- Slow chopper tested with success .
(developed by INFN Catania)


STEP 1: Beam tests results for Deuterons (Saclay)

Ion	Proportion	Courant
Ions	100 %	6.9 mA
H ⁺	2.1 %	0,15 mA
H ₂ ⁺	0.5 %	0.035 mA
D ⁺	83 %	5.8 mA
D ₂ ⁺	9.7 %	0.68 mA
D ₃ ⁺	0 %	0 mA
Ions lourds	3.5 %	0.25 mA



Nominal emittance : $\sim 0.18 \pi \text{ mm.mrad rms norm}$
 Emittance = key parameter for the Linac !!


STEP1: Last result with deuterons in 2012



$\varepsilon_{xx'}$	0.23 $\pi \cdot \text{mm} \cdot \text{mrad}$
$\beta_{xx'}$	0.095 $\pi \cdot \text{mm/mrad}$
$\alpha_{xx'}$	0.99
$\varepsilon_{yy'}$	0.22 $\pi \cdot \text{mm} \cdot \text{mrad}$
$\beta_{yy'}$	0.10 $\pi \cdot \text{mm/mrad}$
$\alpha_{yy'}$	1.17



Real beam matched to RFQ and emittance measurement

Measured emittance
RFQ entrance




Generation of particles
using TRACEWIN...

... send to RFQ model...
Acceleration + bunching




Emittance at
RFQ exit




STEP 2: Injector beam commissioning at SPIRAL2 (Dec. 2014 - June 2015)



- Accepts **future 1/6 beams** Injector
- **Fast chopper** and deviated beam stop.
- Protect the linac against **halo**
→ 3 sets of *H-V slits*
- **Match all types of beams** to linac
- Non interceptive **measurement of beam intensity** at Linac Entrance



STEP 2 : Diagnostic plate (IPHC + IPNO + GANIL)




Development and
mechanical Integration
at IPHC Strasbourg

Diag-plate installation at
GANIL (last week)

STEP 2 : Diagnostic plate (IPHC + IPNO + GANIL)

□ Characterize RFQ beams

- ✓ Current (RFQ transmission)
- ✓ Energy (ToF)
- ✓ Transverse emittances
- ✓ Longitudinal emittance (3-gradients method)



- ➊ : BPM de type LINAC ;
- ➋ : électrode ToF et mesure de courant par FCT ;
- ➌ : profileur MIGR (ionisation gaz résiduel) et profileur EMS (à fils) ;
- ➍ : émittance-mètres H&V, CF rapide et moniteur longueur de paquet ;
- ➎ : CF lente et fentes H&V de nettoyage ;
- ➏ : BPM de type LINAC
- ➐ : 2 électrodes ToF ;
- ➑ : mesure de courant par DCCT+ ACCT.

□ Prepare linac commissioning

- ✓ Characterize the operation of the beam diagnostics tb used in the SC linac with (low-energy) beams.
In particular: Beam Position Monitors (position, phase, ellipticity...), Bunch Extension Monitors...
- ✓ Practice the cavity (V, ϕ) tuning procedure (buncher)

STEP 2: Injector beam commissioning at SPIRAL2 (Dec. 2014 - June 2015)

Planned beams:

Protons ($A/Q=1$)

- 150 μ A peak, 200 μ s pulsed@5Hz (0.1% duty cycle),
- Increase the peak current from 150 μ A to **5mA**, with duty cycle from 0.1% to 100%

Helium $^4He^{2+}$ ($A/Q=2$)

- 150 μ A peak, 500 μ s pulsed @2Hz (0.1% duty cycle),
- Increase the peak current from 150 μ A to **2.4mA**, with duty cycle from 0.1% to 100%

Oxygen $^{18}O^{6+}$ ($A/Q=3$)

- *Pencil beam* 150 μ A peak, 500 μ s pulsed @2Hz (0.1% duty cycle),
- Increase the peak current from 150 μ A to **1mA**, with duty cycle from 0.1% to 100%


If enough time:

- **Argon, Carbon, Xenon**
- **Nickel** $^{58}Ni^{19+}$ up to 20 μ A

... and finally Deuteron beam when full authorization obtained !!!


STEP 3: LINAC + HEBT1 beam commissioning (>2015)

MEBT




Deuterons 5 mA , 40 MeV

1/6 MEBT



$q/A=1/3$, 1 mA , 14.5 MeV/A



$q/A=1/3$ 1 mA , 2 MeV/A


$q/A=1/6$ 1 mA , 7 MeV/A
(In the future ..)

- Knowledge acquired before...
- Efficiency of TRACEWIN code
- 3D calculated and/or measured cavity and quadrupole maps
- 19 BPMs, 6 BEM, many BLMs along the Linac
- ToF, ACCT/DCCT, profilers, loss rings BLMs along the HEBT...

STEP 3: LINAC + HEBT1 beam commissioning (>2015)


□ Pre-tuning of the full MEBT

- ✓ Transverse pre-tuning
- ✓ Longitudinal pre-tuning



□ Create the SC linac periodic channel, step by step


- ✓ Adjust all the linac and HEBT1 quadrupoles for RFQ energy
- ✓ Tune the first cavity (amplitude & phase)
using BPMs (ToF method)
- ✓ Re-adjust all linac quadrupoles
- ✓ Tune the second cavity
- ✓ And so on for the 26 cavities...



STEP 3: HEBT1 from Linac to Beam Dump

NFS (STEP 4)

Beam dump (STEP 3)





LINAC

Towards
production building

STEP3: Intensity → locations of ACCT/DCCTs

NON DESTRUCTIVE BEAM INTENSITY MEASUREMENTS

In order to control continuously the intensities and the losses, ACCT and DCCT are set up along the accelerator.




DCCTs : Bergoz NPCT-175-C030-HR
ACCTs : Homemade

The measurements of intensities and transmissions are required for the accelerator tuning and the beam controls for safety.

S. Leloir et al. "MEASUREMENT AND CONTROL OF THE BEAM INTENSITY FOR THE SPIRAL2 ACCELERATOR", IBIC 2013


STEP3: ENERGY → location of TOF pick up



Pick-up 1



Pick-up 2 and 3



End Linac

Beginning HEBT

W. Lecoz et al. "MEASUREMENT AND CONTROL OF THE BEAM ENERGY FOR THE SPIRAL2 ACCELERATOR", IBIC 2013

One interesting Theorem (without space charge...)

- ✓ Consider an accelerator (for example Spiral2...),
- ✓ Consider a tuning of the machine realised for a given beam (q/m) with a given Energy in Mev/u,
- ✓ Suppose we want to tune another beam q'/m' at the same final energy per nucleon,
- ✓ **Then we just to MULTIPLY all the voltages and magnetic fields by the ratio $(q/m)/(q'/m')$ to obtain the new tuning**
- ✓ The theorem is correct in relativistic case !

*Examples : He4 2+ → Deuteron
O16 6+ → any heavy ion...*

CONCLUSION

The **beam pre-commissioning** performed at IRFU/Saclay and LPSC/Grenoble was essential:

- to make our labs work together in many domains
- to validate our low energy design and simulations,
- to operate many technical tests with the EPICS philosophy and our Command/Control.
- to gain time during full commissioning at GANIL

We enter now in the **complete beam commissioning**, which constitutes a great motivation for all our partners and for us.



THANK YOU !