



# The Design and Commissioning of the Accelerator System of the Rare Isotope Re-accelerator - ReA3

Xiaoyu Wu

NSCL/FRIB

Michigan State University

On Behalf of the ReA3 Team



MICHIGAN STATE  
UNIVERSITY




# NSCL and FRIB Laboratory at Michigan State University

- NSCL is funded by the U.S. National Science Foundation as a user facility to produce rare isotope beams for research and education in nuclear science, nuclear astrophysics, accelerator physics, and societal applications
- FRIB, currently being designed and established at MSU, will be a national user facility funded by the U.S. Department of Energy Office of Science
- NSCL will transition into FRIB eventually



U.S. Department of Energy Office of Science  
National Science Foundation  
Michigan State University

# Rare Isotope Beam Productions by Projectile Fragmentation



# Strong Demands for High Quality, Low-Energy RIBs

- Nuclear astrophysics

- Better interpretation of X-ray bursts and novae observations
- Origin of p-nuclei
- Supernovae modeling

- High quality low energy RIBs allow:

- Reaction measurements at astrophysical energies
- Indirect techniques to obtain astrophysical rates


- Nuclear physics

- Shell structure evolution away from stability
- Understanding pairing, shapes, cluster structure and collectivity of exotic nuclei
- Reaction of exotic nuclei


- High quality low energy RIBs allow:

- Transfer reactions
- Multi-step Coulomb excitation
- Fusion evaporation reactions


# Current NSCL Facility Layout



# Future FRIB Layout




# 3MeV/u Re-accelerator - ReA3 Layout



# LEBT/RFQ


Offline Ion Source

( ${}^4\text{He}^{1+}$ )



Faraday cup

Bunch length monitor



Multi-harmonic  
buncher

Beam transport to the RFQ:



- Beam bunching
- Transverse beam matching

# ReA3 SRF Cryomodules


## ReA3 -

- 3 ReA3 Cryomodules
- 15 cavities
- 2 cavity types (QWR)
  - Beta=0.041 & 0.085
  - Prototypes for FRIB
- 8 solenoids
  - Same as used in FRIB
- 1<sup>st</sup> two cryomodules installed In 2010
- 3<sup>rd</sup> cryomodule under development, will be installed Early 2013

$\beta = 0.041$  modules





$\beta = 0.085$  module




# Design Changes of $\beta=0.085$ QWR

- Old design modified to improve performance reliability
- New design of the rf joint
- Rf couplers moved to the side
- Increased distance from inner conductor to tuning plate



Both ReA3 and FRIB requirements more than fulfilled in testing naked cavities with the new rf joint design and side coupler

# ReA3 beam Distribution Line




Single cavity  
rebunching cryomodule



U.S. Department of Energy Office of Science  
National Science Foundation  
Michigan State University


# ReA3 Beam Dynamics Simulations (1)

*Maintain beam quality – minimize emittance growth*



# ReA3 Beam Dynamics Simulations (2)

## *Meeting beam-on-target requirements*




Beam size:  $\sim 2\text{mm}$


Energy spread:  $\sim 1 \text{ keV/u}$

Bunch length:  $\sim 1 \text{ ns}$


# ReA3 Commissioning ongoing



# Energy Upgrade Phase I - ReA6




# ReA6 Accelerating Cryomodules



- 4<sup>th</sup> generation beta=0.085 QWR cavities
- 8 cavities
- 3 SC solenoid magnets with X/Y dipole correctors
- 3 Cold beam position monitors
- ~ 6 m long
- FRIB Linac Segment I will use same cryomodules (11)


# ReA6 Beam Dynamics Simulations (1)

*Maintain beam quality – minimize emittance growth*




# ReA6 Beam Dynamics Simulations (2)

## *Meeting beam-on-target requirements*




Beam size:  $\sim 2\text{mm}$   
Energy spread:  $\sim 1 \text{ keV/u}$   
Bunch length:  $\sim 1 \text{ ns}$

# Energy Upgrade Phase II - ReA12



# ReA3/ReA6/ReA12 Performance



# Summary

- The Re-Accelerators at the NSCL will provide a new low energy high quality RIBs facility for nuclear astrophysics and nuclear science.
- Construction and commissioning underway.
- Installation of ReA3 completed FY2013
- Radioactive ion beam commissioning runs 2013
- First beamline into ReA3 hall 5/2013
- Energy upgrade phase I started
  - ReA6 Cryomodule fabrication has started, completion planned 2014