

Status of the Free Electron Laser User Facility FLASH

M. Vogt, B. Faatz, J. Feldhaus,
K. Honkavaara, S. Schreiber, R. Treusch



Deutsches Elektronensynchrotron, DESY, Hamburg, Germany

- The Upgraded FLASH Facility
- RF-gun Issues
- User Operation
- FLASH2: First Commissioning
- Highlights




FLASH...

- . . . means
Free electron LASer in Hamburg
- **XUV and soft X-ray SASE FEL**
SASE= self amplified spontaneous emission
- ⇒ **peak brilliance:** $10^{29} - 10^{31}$
photons/(s mm² mrad² 0.1%bw)
- ⇒ **γ pulse duration:** <30 - 200 fs
- **Superconducting L-band linac:**
E up to 1.25 GeV
- ⇒ **up to 8000 bunches per second**
- Every year attracts more than 100 scientists from all over the world
- So far more than 200 publications, partly in highly ranked journals



The (Upgraded) FLASH Facility



- 2 separate photo injector lasers
- warm 1.6 cell RF gun (L-band)
- 1st cold module (ACC1)
 - + 1st bunch compressor chicane
- 2 more cold modules (ACC2+3)
 - + 2nd bunch compressor chicane
- main linac (ACC4+5+6+7)
- 2 beamlines :
 - FLASH1 (since 2005)
 - New 2nd beamline : FLASH2**
- commissioning ongoing


FLASH parameters 2013/2014

e⁻ :		
emittance (1 nC, on-crest, 90% rms)	$\beta\gamma\varepsilon_{x,y}$	1.4 mm mrad
charge	0.08 - 1.0	nC
peak current	0.8 - 2.0	kA
beam energy	380 - 1250	MeV
bunches / train	1 - 450	
bunch spacing	1 - 25	μ s
train repetition frequency	10	Hz
γ (FLASH1 only):		
wavelength (fundamental)	4.2 - 45	nm
average single pulse energy	10 - 540	μ J
pulse duration (fwhm)	<30 - 200	fs
spectral width (fwhm)	0.7 - 2.0	%
peak power	1 - 3	GW
peak brilliance	$10^{29} - 10^{31}$	(+)

(+) : photons/(s mm² mrad² 0.1%bw)


SCRF

Vectorsum Amplitude ACC45:



- RF-Pulse rep. rate: **10 Hz**
- nominal flat top duration: **800 μ s**
- with fill time: duty factor 1.5%
- At **1 MHz** bunch frequency
→ **8000 bu/s**
in 10 trains of 800 bu each


- $7 \times$ SC L-band modules
 - ... of various designs, ages, gradients
- E gain/module : 160 MeV (older) to 240 MeV (X-FEL prototype!)
- $1 \times$ 3rd harmonic (3.9 GHz) module for linearizing the compr.



Fotoshooting bei DESY FLASH-Tunnel, Februar 2012
Foto: Heiner Müller-Essner


E /MeV	1st chic.	2nd chic.	E_{final}
	150	450	380 - 1250

SCRF for 2 (or more) Beamlines





this example ↑:

- 1st sub train to FLASH2
← sparse pattern
- 2nd sub train to FLASH1
← dense pattern
- > 30 μs gap for kicker
 $\sim 50 \mu\text{s}$ gap for RF ↓



- long RF flat tops capable of acc. 800 bunches
- split each train and divide between 2 (or more beamlines)
- 2 lasers :
 - 2 bunch patterns
 - 2 bunch charges
- ← needs 2 compression modes
- ⇒ split flat tops
- tested w/ two different charges // compr. schemes → **SASE**
- 3rd flat top : see plasma wake field proposal FLASHForward → TUPME066 & TUPME068


New: **Switch Yard FLASH1/FLASH2**



- Switches in **each** flat top
- Gap $\sim 30 \mu\text{s}$
- 2× **vertical** kicker (+1 spare)
 - flat top extremely stable
 - very little ringing!
- optics (3 quads)
 - ⇒ 20 mm **v**-separation at septum
- **horizontally** deflecting
 - Lambertson septum : 6.5°

Seeding / Special Diagnostics (FLASH1)

Transverse Deflecting Structure (LOLA):



Seeding:

- sFLASH experiment :
 - HHG (High Harmonic Generation)
- now also test bench for
 - HGHG
(High Gain Harmonic Generation)
 - EEHG
(Echo Enabled Harmonic Generation)
- Decision on seeding scheme for **FLASH2** still pending

→ vertical streak / 2 modes:

1: **minimally invasive → live**

→ kick selected bunch to off-axis screen


→ only bunch length measurement

2: **dispersive → destructive:**


→ horizontal dipole (spectrometer)

→ long. phase space mapped to $x-y$ space


Longitudinal phase space (LOLA phase -12°)
2012-10-10T110805-image-SDUMP




Projected energy deviation




Longitudinal bunch profile



Slice energy spread



User Operation (FLASH1 only)



User Requests 2013/2014

- 2013 :
 - long shutdown
 - ← FLASH2
- 2014 :
 - planned 24 weeks of γ -user operation
- remaining time:
 - FLASH2 commissioning
 - MD's, user preparation

all wavelengths : 40 nm down to 4.2 nm


Pulse Pattern	2013/14	
Single Bunch	47%	
Multi Bunch	53 %	35% > 200 b.
Bunch Spacing	1 MHz 200 kHz other	30 % 43 % 40, 100, 250, 500 kHz

FEL pulse duration (FWHM)


< 50 fs	42%	56% multi bunch
50 - 100 fs	33%	64% single bunch
not critical	26%	83% max energy

Highlights: New Low Level RF System Commissioned

- Long flat top
⇒ fancy regulation →
- New LLRF system :
→ μ TCA.4 based
← X-FEL standard
- After commissioning:
→ higher sampling rate
→ effective energy jitter
(intra train & train to train)
reduced by factor ~ 2 .




Highlights: Relaxed Optics in Main Linac



- Matching into modified optic in switch yard
 - Was **doublet**
 - Is **FODO** now
 - **Improved chromatic behavior**
- Took the opportunity to relax optics in main linac

Highlights: New SASE Pulse Energy Record

- With improved optics ...
- ... and of course after skillful expert tuning:
- New record in pulse energy : **540 μ J at 8.7 nm**
- with 1 bunch of 0.6nC.




RF-Gun Issues

With increased average power (since 2010) the RF gun causes non-negligible downtime:


- Bursts of vacuum, light and multipacting close to the vacuum side of the RF window

→ testing new window types




- discharge in gap between back plane and cathode plug
 - destroys the RF contact and the cavity back plane
- testing new spring / back plane design (old ↓)

Cathode Plug at the rf gun back plane




FLASH2



FLASH2 Commissioning

- Delayed by late construction of the buildings and infrastructure
- Official permission to operate FLASH2 : February 7th 2014
- **First beam extracted** through septum on March 4th
- Top left: screen right before the septum with the FLASH1 beam (bottom) and the FLASH2 beam (top)
- **First beam on the FLASH2 dump** on May 23th
- Bottom left: beam on dump screen
- Always: ran FLASH2 in parallel to FLASH1



Summary / Conclusion / Outlook

- FLASH (FLASH1) provides up to 8000 photon pulses/s in the wavelength range from 45 nm down to 4.2 nm and with pulse durations from 200 fs down to < 30 fs.
- With increased average power (since 2010) the RF gun causes non-negligible downtime:
 - ← The 2 main problems have been identified and are being investigated (component redesign).
- A 2nd beamline has been connected to FLASH. Commissioning is still ongoing.
- The modifications to FLASH1 necessary for operating FLASH2 have so far rather improved the FLASH1 performance:
 - New intensity record of 540 μJ
- We are looking forward to proceed commissioning FLASH2 and to operating FLASH with two beamlines.

I (we) would like to thank all the colleagues at DESY and from the collaborating institutes for their continuous dedication in operation, maintenance and upgrade of FLASH and in particular during the construction and commissioning of the FLASH2 beamline !!!

... and of course thank **you** for Listening !!!

More Talks and Posters on/related to FLASH

Injector:

THPRO043,044

LLRF:

TUPRI105

TUPRI107

WEPME066 ... 069

WEPME075,076

WEPRI115

Diagnostics/ Control System:

WEPRO029

THXA01

THPME106

THPME115

THPME117

THPRO104

Beam Dynamics:

TUPRI040

TUPRO047

TUPRO050

THPME116

Photons:

TUPRO084

WEPRO031,032,034

WEPRO093

THPRO011


FLASHForward:

TUPME066

TUPME068

BACKUP SLIDES

The Photo Injector





- Two independent lasers
→ UV laser pulses of 262 nm
- transversely approximately flat
typical diameter on cathode: 1.2 mm
- longitudinally approximately Gaussian:
 $\sigma = 6 - 7 \text{ ps}$.
- Cs₂Te cathode at cavity back plane

- Normalconducting 1.6 cell 1.3 GHz copper cavity
- Emittance at 1nC $\approx 1.4 \mu\text{m}$
→ smaller at lower charge
- E after gun cavity: 5.2 - 5.7 MeV
- Solenoidal emittance compensation
- ACC1: acceleration to 166 - 169 MeV
($\sim 5^\circ$ off crest)
- ACC39: deceleration to 150 - 147 MeV
→ chirp linearization
- Chicane: compr. by factor ~ 5
- FODO channel : match space charge dominated beam from gun to design Twiss parameters

Compression of Ultra Relativistic Bunches

- magnetic **chicane** ○ off crest RF
= **bunch compressor**
- FLASH : 2× cascaded →
1: BC2 ○ ACC1
2: BC3 ○ ACC23



- small initial uncorrelated E -spread
- ⇒ sinusoidal RF → curved bunch ("banana")
- linearize using 3rd harmonic module (ACC39)

Example : **long!** bunch:

