

Design and Beam Commissioning of the LEAF-RFQ



Liang LU

On behalf of RFQ team, LEAF team

luliang@impcas.ac.cn



Acknowledgements



- Co-authors: W. Ma, X. B. Xu, T. He, L. Yang, C. C. Xing, L. B. Shi, X. F. Jin, L. P. Sun, Y.H. Zhai, Y. Yang, L. T. Sun, Y. He, H. W. Zhao and many others
- We thank our colleagues at IMP: X. F. Jin, B. Zhao, F. F. Wang, X. Fang, Y. H. Guo, L. Jing, P. Zhang, B. Zhang, Z. M. Zhang, X. Z. Zhang, A. M. Shi and many others.
- We also thank T. L. Shen, H. Jia, W. P. Dou, Y. B. Zhao and many other our colleagues for their valuable advice, discussions, and collaborations.
- This material is based upon work supported by the National Natural Science Foundation of China under Cooperative Agreement 11427904. Institute of Modern Physics designs and establishes LEAF as a National Science User Facility in support of the mission of Nuclear Physics and Material Irradiation.




Outline




- RFQ design
- Fabrication and low power test
- RF conditioning
- Beam commissioning and measurement

Prototype of HIAF Frontend



$Xe^{30+}, Bi^{31+}, U^{34+}$	1.5 emA
$^{129}Xe^{45+}$	30-100 μ A
$^{209}Bi^{55+}$	30-100 μ A
$^{238}U^{56+}$	30-100 μ A

Low Energy Accelerator Facility (LEAF)



Low Energy Accelerator Facility (LEAF)


- A pre-research facility for HIAF project;
- Accelerating H_2^+ to U^{34+} in both CW & pulse mode;
- Material irradiation; electron cooling; imagination; et al.;
- Low energy, high intensity; high charged ions; cocktail beam ($H_2^++He^{2+}+^{58}Ni^{28+}$);

ions	current
$^4He^{1+}$	10-15 mA
$^{13}C^{4+}$	1-2 mA
$^{129}Xe^{45+}$	30-100 μ A
$^{209}Bi^{55+}$	30-100 μ A
$^{238}U^{56+}$	30-100 μ A
$H_2^++He^{2+}+^{58}Ni^{28+}$	30-50 μ A


Purpose of using MHB:

- ◆ Decreasing longitudinal emittance
- ◆ Shorten RFQ length


- ◆ frequency: 40.625 MHz, 81.25 MHz, 121.875 MHz
- ◆ Amplitude: 1: -0.23: 0.044



Separatrix @ MHB entrance



Separatrix @ MHB exit




Separatrix @ RFQ entrance

- ◆ The RFQ length was shortened from 7m to 5.96m.

Beam dynamics: cavity parameters

Parameters	Value
Central particle	$^{238}\text{U}^{34+}$
Current (emA)	2
Inter-vane voltage (kV)	70
Kilpatrick	1.56
Input / output energy (MeV/u)	0.014/0.5
R0 (mm)	5.805
Synchronous (deg.)	-45~ -25
Modulation	1.05~2.04
Transverse RMS of input beam ($\text{pi}\cdot\text{mm}\cdot\text{mrad}$)	0.3
Transverse RMS of output beam ($\text{pi}\cdot\text{mm}\cdot\text{mrad}$)	0.293
longitudinal RMS of input beam ($\text{pi}\cdot\text{mm}\cdot\text{mrad}$)	0.098
Cavity length (cm)	596.4





Structure design: vane or rod

Merits of 4-vane type:


- Easy to cooling, stable, CW OK
- High shunt-impedance @ low frequency

Demerits of 4-vane type:

- Bigger structure
- Need mode separation structure



four-vane type RFQ




four-rod type RFQ

Structure design: normal vane or SC vane



Merits of normal 4-vane type:

- Easy to shape and cooling
- Low power density, few deformation
- High Q




Merits of SC-vane type:

- Compact size even in low frequency




Normal vane RFQ



SC RFQ

Structure	Frequency (MHz)	Q	Loss (kw/m)	Vane H (mm)
Four vane	82.4	1.32e4	9.0	360.5
SC	82.6	9.76e3	12.8	225



Feature of inconstant V type:
Increasing V due to decreasing
width of vanes
Bigger surface e field

Merits of normal 4-vane type:
● High Q, lower power loss
● Lower surface e field, lower
SEC

Demerits of normal 4-vane type:
● Longer length


LEAF-RFQ requirements: CW operation → low RF power, low surface E field
Finally normal 4-vane type was chosen.

Structure design: cavity shape


Design principle:

- Resistance to deform. → octagonal shape
- Parametric modeling
- f separation: PISL (π -mode stabilizing loops) structure


Parameters	value
Shape	octagonal
R0	5.805mm
Rv	0.75*R0
θ_1	800
Lv	17mm
θ_2	10°
θ_3	5°
Ws	20mm
Rc	50mm
H	360.5mm




Cross section design





Vane Height & frequency



PISL periodic model



Cross section of cavity with PISL



f separation with 6 pair PISLs




Final separated frequency :

-2.133 MHz


5.548 MHz

Structure design: field tuning

LEAF RFQ tuner



LEAF RFQ under cut



Adopted 48 tuners:


- tuning sensitivity (kHz/mm): 15.21
- tuning ability: -380 kHz~532 kHz

Under cut design:

- D @ entrance: 143mm
- D @ exit: 139mm

LEAF RFQ model

5946.92 mm





length: 5.969m; tuner: 12*4; PISLs: 2*12 pair; with modulation



Parameters of the final model	LEAF RFQ	FRIIB RFQ
frequency (MHz)	81.246	80.5
Q	17963	16500
neighbor dipole mode (MHz)	86.812	78.3/83.2
dissipated RF power (kW)	53.196	100
power loss (kW/m)	8.945	19.8

parts	Power loss
Vanes	4.81 kW/m
Wall	3.18 kW/m
Tuners	42.7 W / tuner
PISLs	144 W / pair

Model for SE simulation



SE: secondary electron



LEAF RFQ 二次电子倍增模拟结果

$$\langle SEY \rangle = I_{emission} / I_{collision}$$

SE multipacting:

- Surface damage
- RF instable, total reflection
- Bad vacuum

Emission electron


Collision electron

Multipacting judgement:


$$\langle SEY \rangle > 1 \text{ or } < 1$$

$\langle SEY \rangle$ was less than 1 in full RF operation
ARC were not observed in RF conditioning

Structure design: whole length model simulation





B: Steady-State Thermal
 Figure
 Type: Temperature
 Unit: °C
 Time: 1
 2017/4/15 19:09
 22.687 Max
 22.391
 22.095
 21.798
 21.502
 21.206
 20.91
 20.614
 20.318
 20.022 Min





Thermal

C: Static Structural
 Total Deformation
 Type: Total Deformation
 Unit: μm
 Time: 1
 Custom
 Max: 21.377
 Min: 0.0020629



A: Deformation


C: Static Structural
 Equivalent Stress
 Type: Equivalent (von-Mises) Stress
 Unit: MPa
 Time: 1
 Custom
 Max: 10.987
 Min: 0.46677




B: Stress

- Max. T: 22.7°C
rised 2.7 °C (water 20 °C)
- max deform.: 21.4 μm
- max. stress: 10.99 MPa
- Δ f: -17.9 kHz

thermal, deformation,
stress and frequency
shifting were
acceptable



Parameters	Value
Particle	U34+ (center q, $q/A=1/7$)
Operation	CW
Vane type	Four vane
Frequency (MHz)	81.25
Input energy (keV/u)	14
Output energy (MeV/u)	0.5
Inter-vane voltage (kV)	70
Peak current (emA)	2
Kp. factor	1.55



- 5.96m; octagon shape; 6 segments; 48 tuners; two couplers; 9 pump ports;
- PISLs were designed to separate the dipole mode; under-cuts were used to adjust field distribution.

Measurements of segments





Image of measuring


Items	Seg.1	Seg.2	Seg.3	Seg.4	Seg.5	Seg.6
frequency	f-designed	81.2596	81.2103	81.2062	81.2192	81.2192
	f-before brazing	81.3035	81.2250	81.1678	81.2310	81.2209
	f-after brazing	81.2437	81.2048	81.1680	81.1967	81.2005
	Δf	-15.9	-5.5	-38.2	-22.5	-18.7
Q	Q-designed	14457	15517	15525	15532	15526
	Q-before brazing	8344(Cu)	7040(Al)	8100(Cu)	7839(Al)	7918 (Al)
	Q-after brazing	9020(Cu)	8200(Al)	7900(Al)	7930 (Al)	7370 (Al)
	Q%	62.4	52.8	50.9	51.1	47.5
f unit: MHz		1 Al end-cup		2 Al end-cups		Al Cu: tuner material

- Perturbation method was used in the low power test;
- Both the frequency and field distribution were very good;
- Q values were very low because of adopting Al end cups and Al tuners;



Items	Measured @ KL	Measured @ IMP	Δ
frequency	81.24526 MHz	81.25346 MHz	3.46 kHz to design
Q_0	75.3% (Al end-cups + Al tuners)	90.37%	15.1%
Flat of Q field	<0.5%	<0.8%	-0.3%
Flat of D field	<1.5%	<1%	0.5%



Measurements of full length RFQ




Measured Results






- Target frequency was measured 81.25346MHz, only 3kHz different
- 5.87 MHz separated

Measured Results




- The flat of Q field is lower than 0.8%, the flat of D field is lower than 1% ;
- Measurements @ KL is better than IMP, but it is good enough for RF power load and beam acceleration ;






LEAF RFQ vacuum



High RF Conditioning process of LEAF RFQ


- Achieved CW 75 kW in 44h;
- Heavy/continuous Arc and multi-parkting are not observed;
- Final vacuum achieved 3e-6 Pa;



X ray measurement

➤ 测量方法:

- ✓ CdTe detector for X ray;
- ✓ high energy region.




Fitting of voltage and RF power

➤ 测量结果:

- ✓ Achieved 70kV when input RF is 66.8kW (designed value is 53kW@cavity + 90%@Q+7kW@beam);
- ✓ Coupling factor is 1.1

LEAF Diagnostics

LEAF - Beam Diagnostics GUI

[Go back v1.0](#)
[Help](#)


Transverse Emittance & Profile (FC)


Longitudinal Bunch Length (FFC)

Beam Energy /TOF (BPM)

Energy Spectrum (Silicon)


Copyright © Beam Feedback Group

Measurements: He⁺ beam




Measurements from ACCTs

- **Measured 97.2% transmission** matched the design;
- **Measured 500keV/u beam energy** agreed well with the design;




Signals from BPMs

Measurements: He⁺ beam




- Both the measurements and the simulations agreed well in both transmission efficiency and acceleration efficiency, under the condition of absence of the MHB.





- Acceleration efficiency was about 50% because of absence of the MHB (multi-harmonic buncher);
- **Long time CW He $^+$ beam operation has been carried out for several months ;**

Measurements: N²⁺ beam




➤ measured beam energy was 500keV/u;

Measurements: N²⁺ beam



- **Measured 98% transmission** matched the design;
- **Measured 54.2% acceleration efficiency** (without the MHB, input current: $108.6\mu A$, and $58.9\mu A$ was measured at FC);



MHB was already offline-tested and installed between two solenoid before the RFQ



Summary



- LEAF facility has been successfully commissioned with 4He^+ and $^{14}\text{N}^{2+}$
 - ◆ LEAF facility is in operation for users (He^+ beam irradiation for material research)
- Beam energy of 500keV/u reliably demonstrated, agrees the designs
- Beam properties are consistent with calculations, satisfy requirements
- All components operate reliably and as expected
- Diagnostics and MPS verified
- MHB is already installed and ready to operate
- Heavy ion test (O, Ar, Kr) proceeds according to the established experimental chamber and schedule

Thank you very much!